Affordable, Replicable and Marketable Net Zero Ready MURBs

Analysis by Wil Beardmore, Bluewater Energy with supporting documentation from Andrew Beacom, Priority Submetering Solutions



Project Objective

To validate the use of panelized/modular construction and integrated mechanical system technologies, design and construction practices on <u>Net Zero or Net Zero</u> <u>Ready MURBs</u> to optimize energy efficient performance, <u>reduce costs</u>, increase construction productivity and reduce construction schedules.

<u>Specifically:</u> Should Net Zero MURBs use one or multiple PV arrays and points of connection to the utility grid?



SINGLE VS. MULTIPLE CONNECTION POINT COMPARISON





Project Comparison Specs



	PV Modules	DC Capacity	Inverters	AC Cacpaity	Transformer
Unit Level x 12	384	138.24kW	12	120kW	0
MURB Level	384	138.24kW	2	125.2kW	1

- 12 x units connecting 11.52kW DC / 10.0kW AC to each unit individually
- MURB connection

 138.24kW DC / 125.2kW
 AC to single connection
 point with Suite Level Sub Metering





etzerc

The ultimate in comfort



	Unit Level 12 x 10kW		MURB Level 120kW		
Design and Permitting					
Utility Connection Fees	\$	9,600	\$	10,000	
Project Design	\$	400	\$	2,000	
Electrical Engineering	\$	-	\$	2,500	
CIA Application Fee	\$	-	\$	6,000	
ESA Plans Review	\$	-	\$	1,200	
Structural Engineering	\$	9,000	\$	3,000	
Building Permit	\$	3,600	\$	1,500	
Electrical Permit	\$	3,840	\$	1,600	
Sub-Total	\$	26,440	\$	27,800	

Ontario Specific – Check Local Utility Costs for your Jurisdiction/ Province



Solar PV Equipment



	Unit Level 12 x 10kW	Ι	MURB Level 120kW	
Solar PV Equipment				
Solar Modules	\$ 103,680	\$	103,680	
Inverters	\$ 62,400	\$	28,000	
Mounting System	\$ 24,960	\$	24,960	
Wire/Cable/Conduit	\$ 13,824	\$	6,912	
Panels/Combiners/Disconnect	\$ 2,340	\$	6,500	
Transformer	\$ -	\$	9,500	
Sub-Total	\$ 207,204	\$	179,552	13.3%



Mechanical Install



		Unit Level 12 x 10kW		MURB Level 120kW	
Mechanical Installation					
Rooftop Solar Installation	\$	47,002	\$	35,942	
Equipment Rental	\$	12,150	\$	4,320	
Sub-Total	\$	59,152	\$	40,262	31.9



Connection & Commissioning



		Unit Level 12 x 10kW		MURB Level 120kW	
Connection and Commissioning					
Safety Switch	\$	4,500	\$	3,500	
AC Connection Equip	\$	2,100	\$	10,368	
Electrical Connections	\$	18,240	\$	12,825	
Monitoring Set-up	\$	2,100	\$	1,500	
System Commissioning	\$	1,440	\$	1,500	
Post Installation Engineer Review	\$	-	\$	1,500	
Suite Level Sub-Metering	\$	-	\$	3,200	
Sub-Total	\$	28,380	\$	34,393	-21.2%



Total Project Costs



	Unit Level		MURB Level	
	12 x 10kW		120kW	
Total Cost	\$ 317,576	\$	282,007	
Cost Per Watt	\$ 2.30	\$	2.04	
Difference		\$	35,568	11.2%





Additional Comments

Individual Suite-Level Connections

- Homeowner owns system and is responsible for system maintenance and performance
- No ongoing relationship with homeowner post close
- PV credits are tracked and reconciled with homeowner by utility

MURB Single Connection Point

- Third Party Entity owns PV system and is responsible for system maintenance and performance
- Ongoing sub-metering relationship with tenant or homeowner for billing
- PV credits must be manually tracked and allocated to individual suites





Thank you to the following partners who are making this project possible:









And the consultants who are helping:







